

SURVEY &
REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>39W</u>	<u>C-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register's Office }
Gogebic County } ss.

Received for record the
17TH day of MARCH
A. D. 1998 at 9:50 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 314
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

Section Corner 5, 6, 7 & 8; T.44 N., R.39 W.

I, Richard L. Drahn in a field survey on December 8, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3		●										
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wells Burt on 8/30/1851. Original B.T.s --- Hemlock 20" S.57 E. 27 links (17.82') --- Hemlock 10" S.80 W. 4 links (2.64') ---

Corner monumented by Donald D. Lappala (12585) at the location of a cedar stake and a natural feature tie. GLO B.T.s destroyed by road construction. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following:

6"	Red Maple	S.24 E.	42.4'
7"	Red Maple	S.27½ W.	27.2'
10"	Hemlock	S.63½ W.	34.6'

Corner recorded in USFS Liber, Page E-5 on 5/6/63.
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered Lappalas' monument as described and his B.T.s as follows:

10"	Red Maple	S.24 E.	42.39'
12"	Red Maple	S.26 W.	27.08'
13"	Hemlock	S.63 W.	34.63'

No evidence of the original B.T.s remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

5"	Yellow Birch	N.10 W.	24.08'
4"X4"	Cedar sign post	S.52 W.	0.40'
7'	Steel sign post	S.06 W.	1.48'

PEER GROUP APPROVED
Richard L. Drahn 12/19/97
COUNTY REGISTER



Signed by Richard L. Drahn Date December 12, 1997

Surveyor's Michigan License No. 21564