

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Gogebic Located In: Corner Code #  
 (County)

1. Public Land Survey T44N R 39W C-10  
 T\_\_\_ R\_\_\_  
 T\_\_\_ R\_\_\_  
 T\_\_\_ R\_\_\_

2. Property Controlling S\_\_\_ T\_\_\_ R\_\_\_  
 in Section S\_\_\_ T\_\_\_ R\_\_\_

3. Miscellaneous S\_\_\_ T\_\_\_ R\_\_\_  
 Property in Sec. S\_\_\_ T\_\_\_ R\_\_\_

**SURVEY & REMONUMENTATION**  
**JAN 05 2001**  
**SECTION**

Register's Office } ss.  
 Gogebic County }

Received for record the  
2<sup>ND</sup> day of JUNE  
 A. D. 19 00. at 10:20 o'clock  
4 m., and recorded in  
 Liber 7 of CORNERS  
 on page 345  
*Cheryl Ruppe, Dep*  
 Register of Deeds  
 Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 Quarter Corner common to Sections 29 & 30.

I, John R. Garske, in a field survey on April 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4			3		2		1
3													
4	7			8		9			10		11		12
5													
6	18			17		16			15		14		13
7													
8	19			20		21			22		23		24
9													
10	30			29		28			27		26		25
11													
12	31			32		33			34		35		36
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**  
 Corner established by Wells Burt, U.S. Deputy Surveyor, in 1851.  
 Original Bearing Trees: 12" White Birch N 83° W 26 Links  
 16" Sugar Maple S 27° W 18 Links

1965-Donald Laapala RLS #12585 set 2" x 45' concrete filled galvanized iron pipe capped with a 3" bronze cap witnessed by the following:  
 8" yellow birch N21W 18.3 feet  
 3" hemlock N36E 16.5 feet  
 4" sugar maple S76E 17.2 feet  
 Rec. May 31<sup>st</sup> 1966 in USFS BK #1 pg. 137 under index #T-5.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 I found a 2" iron pipe capped with stamped brass cap marking the location of the quarter corner common to Sections 29 and 30.  
 I accepted Lappala corner and established new accessories as noted below.

(Record Research on File)

**DEED GROUP APPROVED**  
*Richard R. Drake* 5/25/00  
 COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 I accepted the above described 2" iron pipe as the proper corner and established the following witnesses:  
 Steel sign post West 1.48 Feet  
 12" Hemlock N 42° E 16.57 Feet (existing)  
 4" Sugar Maple S 69° E 17.32 Feet (existing)  
 16" Oak S 62° W 35.66 Feet  
 6" Sugar Maple N 25° W 37.70 Feet

Signed by John R. Garske  
 Surveyor's Michigan License No. 28410



Date 5/25/00