

**SURVEY &  
REMONUMENTATION**

SEP 08 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>39W</u>	<u>C-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner 29, 30, 31 & 32; T.44 N., R 39 W.

Richard L. Drahn in a field survey on December 7, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wells Burt on 8/27/1851. Original B.T.s --- Black Oak 10" N.13 W. 12 links (7.92') --- W. Birch 10" S.44 E. 16 links (10.56')---

Corner restored on 7/3/62 by Donald D. Lappala (12585) at the site of the original corner tree (7" W. Pine) and from the stump remains of the original Oak B.T. He set a 2" X 5' iron pipe with a 3" stamped brass cap and:

- 5' Black Oak N.79 W. 40.7'
- 6" Black Oak N.04 W. 8.5'
- 4" Black Oak S.82½ E. 9.9'

Corner recorded in Gogebic County USFS Liber, Page V-5 on 5/6/63.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered Lappalas' monument as described and his bearing trees as follows:

- 13" Northern Red Oak N.80 W. 40.71'
- 11" Northern Red Oak N.04 W. 8.46'
- 7" Northern Red Oak S.83 E. 9.83'

The Black Oak at N.13 W. is now a very badly decayed Oak stump with several large oak sprouts. No evidence remains of the original corner tree or the original W. Birch B.T.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

- 6' Steel sign rail S.01 W. 1.38'
- 4"X4" Cedar sign post N.51 W. 4.56'

**PEER GROUP APPROVED**  
Richard L. Drahn 12/19/97  
**COUNTY REGISTER**

Signed by Richard L. Drahn Date December 12, 1997  
Surveyor's Michigan License No. 21564

Register's Office }  
Gogebic County } ss.

Received for record the  
17<sup>TH</sup> day of MARCH  
A. D. 1998 at 9:50 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 315.  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

