

**SURVEY &
REMONUMENTATION**

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic (County) Located In: Corner Code #
 1. Public Land Survey T 44N R 39W D-3
 T ___ R ___
 T ___ R ___
 T ___ R ___
 2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

Register's Office } ss.
Gogebic County }

Received for record the
17TH day of MARCH
A. D. 1998 at 9:50 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 316.
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 5 & 8; T.44 N., R. 39 W.

I, Richard L. Drahn in a field survey on December 8, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3		●										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wells Burt on 9/1/1851. Original B.T.s --- Y. Birch 36" N.33 W. 11 links (7.26') --- Sugar S.49 E. 18 links (11.88') ---
 Corner restored on 6/18/85 by Richard L. Drahn (21564) from the remains of the two original B.T.s, a line tree and dist. east to corner. He set a 2" X 30" alum. pipe with a 3 1/2" stamped alum. cap and the following new B.T.S:

16"	Sugar Maple	N.82 W.	31.97'
12"	Sugar Maple	N.88 E.	36.54'
8"	Sugar Maple	S.26 W.	40.18'
6'	Steel sign post	S.87 E.	2.1'

Corner recorded in Gogebic County in Liber 2, Page 737 on 3/25/86.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered Drahn's monument as described and his B.T.s as follows.

17"	Sugar Maple	N.83 W.	31.97'
12"	Sugar Maple	N.87 E.	36.54'
8"	Sugar Maple	S.26 W.	40.24'
6"	Steel sign rail	S.87 E.	2.14'

A large stump hole still remains from the NW GLO bearing tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

8" Sugar Maple N.06 E. 55.40'

PEER GROUP APPROVED

Richard L. Drahn 12/19/97
COUNTY REGISTER



Signed by Richard L. Drahn Date December 12, 1997

Surveyor's Michigan License No. 21564