

**SURVEY &
REMONUMENTATION**

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION
Gogebic
(County)

1. Public Land Survey	T 44N. R 39W.	D-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }
Gogebic County } ss.

Received for record the
17TH day of MARCH

A. D. 1998 at 9:50 o'clock
A m., and recorded in

Liber 6 of CORNERS
on page 317.

Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 20 & 29; T.44 N., R.39 W.

Richard L. Drahn, in a field survey on December 10, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wells Burt 8/21/1851. Original B.T.s --- Y. Birch
22" S.78 E. 52 links (34.32') --- Y. Birch 12" N.54 W. 32 links (21.12') ---

Corner restored by G.A. Shadko, Mich. Cons. Dept. in 1946.

Corner recovered by Donald D. Iappala (12585) on 6/5/61. Corner listed as a stamped brass cap on a 5" X 5' concrete monument at record bearing and dist. from the remains of the two original B.T.s (SE B.T. was still alive). New B.T.S

6" Sugar Maple N.28 W. 26.1'
8" Red Maple S.01 W. 36.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Power Pole No. N52-1894 S.45 E. 19.6'

Corner recorded in USFS Liber, Page R-7 on 8/29/62.

Corner found broken on 8/15/88 by Gary L. Pisoni (27457) and replaced with a 2" X 36" aluminum pipe with a 3 1/4" stamped aluminum cap and the following:

10" Sugar Maple N.28 W. 26.08'
13" Sugar Maple N.47 E. 49.05'
9" Red Maple S.02 W. 36.87'
Wood sign post S.80 E. 4.6'
Steel sign post N.47 E. 0.69'

Corner recorded in Gogebic County in Liber 3, Page 269 on 11/30/88.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described aluminum monument I recovered or referenced:

11" Sugar Maple N.29 W. 26.05'
15" Sugar Maple N.47 E. 49.10'
10" Red Maple S.02 W. 36.90'
Wood sign post, wood S.82 E. 4.52'
steel sign post N.46 E. 0.63'
Power Pole No. 82-23542 S.39 E. 25.86'

PEER GROUP APPROVED

Richard L. Drahn 12/19/97
COUNTY REGISTER



Signed by Richard L. Drahn

Date December 11, 1997

Surveyor's Michigan License No. 21564