

SURVEY & REMONUMENTATION

AUG 08 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in	<u>Gogebic</u>	Located In:		Corner Code #	
	(County)				
1. Public Land Survey	Sec. 10	T 44N R 39W		G-5	
		T _____ R _____		_____	
		T _____ R _____		_____	
		T _____ R _____		_____	
2. Property Controlling in Section	S _____	T _____ R _____		_____	
	S _____	T _____ R _____		_____	
3. Miscellaneous Property in Section	S _____	T _____ R _____		_____	
	S _____	T _____ R _____		_____	

Received for record the
16th day of MAY
A. D. 1997 at 11:20 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 131
Ramona L. Collins Deputy
Register of Deeds
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section corner 9, 10, 15 & 16, T44N, R39W.

I, John R. Garske, in a field survey on April 15th, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5							●						
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original corner established by Wells Burt, U.S. surveyor on August 25, 1851.
Original bearing trees: Cedar 10" S 36°E 27 links. Sugar Maple 10" N19°E 11 links.
- Corner position recovered and referenced by E. Kazianka RLS 14765, with a witness monument consisting of a 1" iron pipe with 4" aluminum cap, stamped; Kimberly-Clark Corp.; location is 20 feet North, W.C.; 9/10/15/16; T44N, R39W, and referenced by the following:
 - 14" White Pine N19°W 100.0 feet (Dead, 6/18/85)
 - 12" Aspen S59°E 75.1 feet, on 8/25/70, Donald Lappala RLS 12585 established the following bearing objects;

(see reverse side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the monument set by Richard Drahn and the W.C. set by Kazianka- found all bearing trees established by Drahn and Pisoni to be in good condition. The cedar wood post set by Lappala was down.

(Record research on file)

PEER GROUP APPROVED
Richard L. Drahn 5/12/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I accepted the above mentioned monument and the bearing trees that were established by Drahn and Pisoni. I then established the following reference object: 6' steel sign rail - due south- 0.92 feet.

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 5/12/97

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

4" Cedar Sign post S60°W 1.9 feet
3" White Birch N 65°W 30.7 feet
Wisc-Mich Pole #80-59 N65°E 15.8 feet (cut, 6/18/85)

In 1985 Richard Drahn, RLS. 21564 surveyed the section line between sections 9 & 10 and set, on line and 20 feet northerly of Kazianka's W.C. an 18" long by 2" diameter monument. Cap is stamped to read: T44N, R39W; S-9, S-10, S-15, S-16; RLS 21564; 1985; from which Drahn established the following references: Stop sign post N59°W - 132.2 feet, 6" Red maple N 17°W 65.07 feet, Wisc-Mich pole #73-1506 S06°E 115.52 feet. Rec. L2, pg. 763

In years 1986 - 1988 Gary Pisoni RLS 27457, did a plat of survey for the U.S. Forest Service of Sections 3,4,9, &10 T44N, R39W and recorded at the register of deeds in Gogebic County . (L2, pg763) ~~the register of deeds in gogebic County~~. Gary Pisoni found the monument set by Richard Drahn and the W.C. set by Kazianka and the Red Maple bearing tree. White Birch 7", S78°W, 27.81 feet.

**SURVEY &
REMONUMENTATION**

AUG 08 1997

COMMISSION