

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey		T <sup>4</sup> <del>49</del> N R <sup>39</sup> <del>44</del> W	G-12
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 33 & 34; T. <sup>44</sup> ~~49~~ N., R. <sup>39</sup> ~~44~~ W.

I, Richard L. Drahn in a field survey on December 10, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wells Burt on 8/24/1851. Original B.T.s --- Y. Pine 10" North 47 links (31.02') --- Y. Pine 8" S.04 E. 25 links (16.50')---

Corner monumented by Robert H. Winat (20585) with a 2" X 36" iron pipe and stamped brass cap.

Gary L. Pisoni (27457) recovered Winats' monument on powerline, close to midpoint on the section line. From Winats' monument he established the following new B.T.s:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Jack Pine 8" S.80 E. 32.70'
- Popple 9" S.80 W. 58.17'
- Jack Pine 9" N.61 W. 77.29'
- Steel sign rail 6' South 1.30'

Corner recorded in Gogebic County in Liber 3, Page 266 on 11/30/88.

Research on file with Gogebic County records.

Recovered Winats' monument as described and the B.T.s as follows:

- 10" downed J. Pine S.81 E. ----
- 11" Popple stub S.80 W. 58.20'
- 11" J. Pine N.63 W. 77.34'
- 6' Steel sign rail S.11 E. 1.22'


No evidence remains of the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

- 9" Jack Pine S.78 W. 65.86'
- 3" Red Pine S.60 E. 49.29'

PEER GROUP APPROVED  
Richard L. Drahn 12/19/97  
COUNTY REGISTER



Register's Office }  
Gogebic County } ss.

Received for record the  
17<sup>th</sup> day of MARCH  
A. D. 1998 at 9:50 o'clock  
A m., and recorded in  
Liber 6 of CORNER  
on page 320.  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Signed by Richard L. Drahn Date December 11, 1997

Surveyor's Michigan License No. 21564