

**SURVEY &
REMONUMENTATION**

SEP 08 1998

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>39W</u>	<u>H-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }
Gogebic County } ss.

Received for record the
17TH day of MARCH
A. D. 1998 at 9:50 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 321
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 27 & 34; T.44 N., R.39 W.

Richard L. Drahn in a field survey on December 10, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wells Burt on 8/28/1851. Original B.T.s --- Aspen 6" N.25 W. 14 links (9.24') --- Aspen 5" S.53 E. 2 links (1.32') ---

Corner re-established on 11/19/86 by Gary L. Pisone (27457) by single proportionate methods. He set a 2" X 30" aluminum monument with a 3 $\frac{1}{4}$ " stamped aluminum cap and the following new B.T.s:

10"	Jack Pine	N.15 W.	55.65'
14"	White Pine	N.14 E.	154.50'
	Metal rail	West	0.85'
6'	Metal sign post	South	0.75'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 3, Page 195 on 8/24/88.

Corner research on file with Gogebic County records.

Recovered Pisonis' monument and the B.T.s as follows:

11"	Jack Pine	N.17 W.	55.68'
18"	White Pine	N.12 E.	no dist.
6'	Metal sign post	S.86 W.	0.67'
6'	Metal sign post	S.24 E.	0.77'

No evidence remains of the original B.T.s

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

5"	Red Pine	S.20 W.	4.04'
5"	Red Pine	S.74 E.	18.46'

PEER GROUP APPROVED

Richard L. Drahn 12/19/97
COUNTY REGISTER



Signed by Richard L. Drahn Date December 11, 1997

Surveyor's Michigan License No. 21564