

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gocebic County } ss.

Received for record the
17TH day of MARCH
A. D. 1998 at 9:55 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 322
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gocebic _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>39W</u>	<u>T-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Section Corner 26, 27, 34 & 35; T.44 N., R.39 W.

Richard L. Drahn, in a field survey on December 9, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wells Burt on 8/25/1851. Original B.T.s --- Tamarack 8" S.47 E. 73 links (48.18') --- Tamarack 8" N.87 E. 60 links (39.60') ---

Corner restored on 9/7/62 by Donald D. Lappala (12585) from the remains of the two original B.T.s and natural feature ties. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s:

7"	Jack Pine	N.88 E.	69.0'
6"	Jack Pine	S.18 W.	84.5'
10"	Jack Pine	S.66 W.	89.7'

Corner recorded in Gocebic County in USFS Liber, Page V-17.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gocebic County records.

Recovered Lappalas' corner as described and his B.T.s as follows:

8"	Jack Pine	N.86 E.	dead and down
10"	Jack Pine	S.18 W.	84.51'
10"	Jack Pine	S.64 W.	dead and down

No evidence remains of the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

5"	Tamarack	N.45 E.	42.60'
6"	Jack Pine	S.58 W.	66.32'
6'	Steel sign rail	S.28 E.	3.00'
4" X 4"	Cedar sign post	N.31 W.	2.79'



PEER GROUP APPROVED

Richard L. Drahn 12/19/97
COURT REGISTRAR

Signed by Richard L. Drahn Date December 11, 1997

Surveyor's Michigan License No. 21564