

**SURVEY &
REMONUMENTATION**

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION _____
Gogebic (County)

1. Public Land Survey	T 44N R 39W	J-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register's Office } ss.
Gogebic County }

Received for record the
17TH day of MARCH
A. D. 1998 at 9:55 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 324.

Ramona Bellum
Deputy
Register of Deeds

Register of Deeds Stamp & File Number

$\frac{1}{4}$ Corner 26 & 35; T.44 N., R.39 W.

I, Richard L. Drahn in a field survey on December 9, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wells Burt on 8/29/1851. Original B.T.s --- Spruce 8" North 46 links (30.36') --- W. Pine 10" N.50 W. 61 links (40.26') ---

Corner restored on 7/29/87 by Gary L. Pisoni (27457) from the remains of the White Pine, then a stump with GLO blaze and measuring notch. He set a 3/4" solid aluminum rod with a 3 1/4" stamped aluminum cap and the following:

9"	Jack Pine	N.31 W.	31.96'
7"	Jack Pine	N.08 W.	19.93'
8"	Jack Pine	N.32 E.	30.99'

Corner recorded in Gogebic County in Liber 3, Page 151 on 8/24/88.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Corner research on file with Gogebic County records.

Recovered Pisonis' monument as described and his B.T.s as follows:

11"	Jack Pine	N.31 W.	31.99'
9"	Jack Pine	N.09 W.	19.95'
10"	Jack Pine	N.32 E.	30.98'
6'	Steel sign rail	S.09 W.	1.30'

The White Pine stump from the original survey still has the measuring notch visible. No evidence remains of the original Spruce B.T.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

6"	White Pine	N.71 E.	59.04'
----	------------	---------	--------

PEER GROUP APPROVED

Richard L. Drahn 12/19/97
COUNTY REGISTER



Signed by Richard L. Drahn Date December 11, 1997

Surveyor's Michigan License No. 21564