

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in
Gogebic
(County)

| Located In: | Corner Code # |
|--------------------|---------------|
| Section 13 44W 39W | K-6 |
| T R | |
| T R | |
| T R | |
| T R | |
| S T R | |
| S T R | |
| S T R | |
| S T R | |

Received for record the
24th day of NOVEMBER
A. D. 1997 at 11:40 o'clock
A m., and recorded in
Liber 6 of GOGEBIC
on page 259
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 corner to section 13 & 14, T44N, R39W

I, John R. Garske, in a field survey on October 13^g 87 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- Original corner set by Wells Burt, D.S. in 1851
Original B.T.'s: Y. Birch 20" N63° 22links
Cedar 10" S37°W 17 links
- 10/16/73 corner monumented by Ed Kazianka RLS 14765, set a 1" iron pipe with a 4" dia. alum. cap stamped, from which he established:
6" sugar S78°W 43.23feet
5" sugar N45°E 37.95 feet
- 7/22/85 corner position found by Richard Drahn RLS 21564 at record bearing and distance from remains of the two bearing trees. He updated accessories as noted below Corner recorded L2, pg. 748.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the monument set by Kazianka in 1973 and all of the bearing trees in good condition. I updated the accessories as noted below in section C.

| | | | |
|----------------|-------------|-------|-----------|
| Existing BT's | 15" Hemlock | N47°W | 18.6 feet |
| From Richard | 5" sugar | N63°E | 18.8 feet |
| Drahn's Cert.: | 10" Y.B | S33°W | 43.6 feet |
| | S.S. P. | S54°W | 2.9 feet |

(Research on file)

VEEH GROUP APPROVED
Richard L. Drahn 11/1/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1" iron pipe with 4" dia. alum. cap stamped to identify corner and the following existing bearing trees:

| | | |
|-----------------|-------|-------------------------|
| 18" hemlock | N43°W | 18.25 feet (set nail) |
| 10" sugar | N51°E | 37.82 fet (set nail) |
| 8" sugar | S57°E | 18.80 feet (found nail) |
| 16" y. birch | S35°W | 43.60 feet (found nail) |
| 8' sugar | S82°W | 37.85 fet (found nail) |
| Steel Sign Rail | S60°W | 2.81 feet (existing) |

Measurements to nails in trees.

Signed by John R Garske
Surveyor's Michigan License No. 28410

Date 11/11/97

