

**SURVEY &
REMONUMENTATION**

SEP 08 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }
Gogebic County } ss.

Received for record the
17TH day of MARCH
A. D. 1998 at 9:55 o'clock
A m., and recorded in
Liber 6 of GOGEBIC

on page 325
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> <small>(County)</small>	Located in:	Corner Code #:
1. Public Land Survey	T <u>44N</u> R <u>39W</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Section Corner 25, 26, 35 & 36; T.44 N., R.39 W.

I, Richard L. Drahn, in a field survey on December 9, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wells Burt on 8/22/1851. Original B.T.s --- Y. Pine 20" N.16 E. 19 links (12.54') --- Y. Pine 18" S.09 E. 41 links (27.06') ---

Corner re-established by Gary L. Pisoni (27457) on 9/18/87 using double proportionate methods. He set a 2" X 30" alum.pipe with a 3 1/4" stamped aluminum cap and the following:

- 11" Red Pine N.41 E. 29.80'
- 8" Red Pine S.79 E. 33.40'
- 7" Red Pine S.34 W. 5.34'
- 10" Jack Pine N.68 W. 6.89'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6' Metal sign post North 1.10'
Corner recorded in Gogebic County in Liber 3, Page 159 on 8/24/88.

Corner research on file with Gogebic County records.

Recovered Pisonis' monument as described and his B.T.s as follows:

- 14" Red Pine N.39 E. 29.91'
- 9" Red Pine S.81 E. 33.42'
- 10" Red Pine S.34 W. 5.36'
- 10" Jack Pine N.69 W. 6.89'
- 6' Steel sign rail N.04 E. 1.11'

No evidence of the GLO B.t.s recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- 9" Red Pine N.16 W. 30.98'

PEER GROUP APPROVED
Richard L. Drahn 12/19/97
COUNTY REGISTER



Signed by Richard L. Drahn Date December 12, 1997

Surveyor's Michigan License No. 21564