

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
4TH day of NOVEMBER
A. D. 1998 at 3:20 o'clock
1 p. m., and recorded in
Liber 7 of CORNERS
on page 75.
Rosemary Collins, Deputy
Register of Deeds

For corners in

Gogebic Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 43N R 39W K-1
T 44N R 39W K-13
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sec. 35 and 36, T44N, R39W
Section Corner Sec. 2 and 1, T43N, R39W

I, Gary L. Pisoni, in a field survey on October 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt, U.S. Deputy Surveyor on July 2, 1847.
Original Corner: Tamarack Post

Original Bearing Trees:

Spruce 5" N 57° E 25 lks (16.50 feet)
Spruce 5" N 62° W 25 lks (16.50 feet)

In 1851, Wells Burt, U.S. Deputy Surveyor established two new bearing trees:

Tamarack 4" S 54° W 20 lks (13.20 feet)
Tamarack 4" S 19° E 14 lks (9.24 feet)

On 9/18/87, I restored the corner position by single proportionate measurement on line between the South quarter corner of Section 35 and the South quarter corner of Section 36, and set a 2" diameter by 30" aluminum pipe monument, 2" above ground surface, with a 3" aluminum cap stamped as follows: T44N, R39W, S-35, S-36, S-2, S-1; T43N; 1987; RLS 27457; from which I established the following blazed and scribed bearing trees:

1987 Bearing Trees:

White Birch 8" S 81° E 8.55 feet
Balsam 9" S 20° W 26.63 feet
Black Spruce 7" N 70° W 55.25 feet
Black Spruce 8" N 27° W 44.25 feet
Brass Cap/Winnot 2" pipe N 23° 45'36"W 17.80 feet
Steel sign post North 1.50 feet

DEED GROUP APPROPRIATE
Richard L. Dean 10/27/98
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.'s found

On 10/16/98, found the monument as described above and the following bearing objects: (All measurements taken to a nail in side of tree)

White Birch 8" S 81° E 8.55 feet
Balsam 11" S 20° W 26.63 feet
Black Spruce 8" N 70° W 55.25 feet
Black Spruce 9" N 27° W 44.25 feet
Brass Cap/Winnot 2" pipe N 23° 45'36"W 17.84 feet
Steel sign post North 1.50 feet

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

98-G2

Signed by Gary L. Pisoni Date October 24, 1998

Surveyor's Michigan License No. 27457

