

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
17th day of MARCH
A. D. 1998 at 9:55 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 326

Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic (County)

Located In:

Corner Code #:

1. Public Land Survey

T 44N R 39W M-11

T _____ R _____

T _____ R _____

T 44N R 38W A-11

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner 25, 36, 30 & 31; T.44 N., R.38-39 W.

I, Richard L. Drahn in a field survey on December 9, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 7/2/1847. Original B.T.s --- Sugar 12" S.10 W. 40 links (26.40') --- W. Pine 30" n.25 E. 33 links (21.78') ---

Corner restored by Gary L. Pisoni (27457) on 6/8/87 from the remains of the original White Pine stump. He set a 2" X 30" alum. pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s:

- 7" Sugar Maple N.87 E. 14.08'
- 3" Balsam S.29 E. 17.15'
- 6" Oak S.65 W. 8.05'
- 9" Oak N.28 W. 15.19'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 6' Metal sign post North 1.36'

Corner recorded in Gogebic County in Liber 3, Page 171 on 8/24/88.

Corner research on file with Gogebic County records.

Recovered Pisonis' monument as described and his B.T.s as follows.

- 7" Sugar Maple N.86 E. 14.08'
- Balsam destroyed by road construction
- 8" Northern Red Oak S.65 W. 8.05'
- 10" Northern Red Oak N.30 W. 15.19'
- 6' Steel sign rail N.13 W. 1.29'

Portions of the original White Pine stump still remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- 4" Balsam N.24 E. 24.30'

PEER GROUP APPROVED

Richard L. Drahn 12/19/97
COUNTY REGISTER



Signed by Richard L. Drahn Date December 12, 1997

Surveyor's Michigan License No. 21564