

SURVEY & REMONUMENTATION

JAN 22 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
11TH day of NOVEMBER
A. D. 1997 at 11:40 o'clock
A m., and recorded in
Liber 6 of COGNATE
on page 261
Ramona Collins Deputy
Register of Deeds

SECTION
For corners in
Gogebic
(County)

Located In: Corner Code #
Section 17 44W 39W C-D-5 EAST
T R #002
T R
T R
T R
S T R
S T R
S T R
S T R

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims
M. C. To Section 8 & 17, T44N, R39W on the East Shore of Duck Lake.

John R. Garske October 23, 97

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Wells Burt, D.S. in 1851.
Original corner - 4" cedar tree, B.T: White Birch 12" N70°E - 7 links.
1962 - Donald Lappala, RLS 12585 found the original corner consisting of a 12" cedar tree at record distance from the W. Birch B.T. now 18" diameter. He established bearing trees and set a brass capped pipe 1 foot west of the tree as noted below. Corner recorded L1, pg.731.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I found the original meander corner, now a 14" live cedar tree with a 2" galvanized pipe with a 3" brass cap stamped to identify it as a W.C.M.C., 1.0' west of the corner tree. The W. Birch B.T. is now a 26" diameter 20 foot high stub. I updated the accessories as noted below.


(Research on file)

PEER GROUP APPROVED
Richard R. Deahn 11/11/97
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 14" cedar tree at the meander corner and a stamped 3" brass capped 2" dia. pipe at 1.0' west as a W.C. M.C. from which I established:

14" Hemlock(dead)	N37°E	22.8' (existing)
26" Y. Birch (dead)	N75°E	6.2± (existing)
16" Cedar	S10°E	9.32 feet (existing)
8" Hemlock	S35°W	8.65 feet
Wood Post	S70°W	4.64 feet(existing)
1 1/2" Iron Pipe	N70°W	1.14 feet
Steel Sign Rail	N10°W	1.32 feet



Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 11/11/97