

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
18<sup>TH</sup> day of APRIL  
A. D. 1994 at 1:20 o'clock  
P m., and recorded in  
Liber 5 of CORNERS  
on page 26  
Betty Saari Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in  
Gogebic  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>44N</u> R <u>41W</u>	<u>C-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat PEER GROUP Approved

5. Private Claims \_\_\_\_\_ Richard L. DeBru 4/7/94

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gary L. Pisoni, in a field survey on August 10, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by Algernon Merryweather, U.S. Deputy Surveyor on July 11, 1852.  
Original Corner: Wood Post  
Original Bearing trees:  
Balsam 8" S 40° W 18 links (11.88 feet)  
Hemlock 10" N 70° E 14 links (9.24 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found. Found iron pipe which had been used as the Section corner, but erroneous and too far out of position.  
I restored the corner position using double proportionate measurement methods between the South quarter corner of Section 5 and the Southwest corner of Section 6 and the East quarter corner of Section 6 and the Southeast corner of Section 7.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: T44N, R41W, S-6, S-5, S-7, S-8, 1991, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Sugar Maple	6"	N 36° E	13.86 feet
Sugar Maple	7"	S 70° E	20.57 feet
Sugar Maple	6"	S 81° W	20.13 feet
Steel Sign Post		South	0.82 feet
Iron pipe		N 84° 43' 35" E	76.70 feet



Signed by Gary L. Pisoni Date 3-22-94

Surveyor's Michigan License No. 27457