

**SURVEY & REMONUMENTATION**

SEP 29 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Far corners in Gogebic  
(County)

Located In: Corner Code #

- |                                    |         |                           |            |
|------------------------------------|---------|---------------------------|------------|
| 1. Public Land Survey              | Sec. 15 | T <u>44N</u> R <u>41W</u> | <u>H-7</u> |
|                                    |         | T _____ R _____           | _____      |
|                                    |         | T _____ R _____           | _____      |
|                                    |         | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ | T _____ R _____           | _____      |
|                                    | S _____ | T _____ R _____           | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ | T _____ R _____           | _____      |
|                                    | S _____ | T _____ R _____           | _____      |

Register's Office  
Gogebic County

Received for record the  
16<sup>TH</sup> day of SEPTEMBER  
A. D. 1994 at 3:20 o'clock  
P m., and recorded in  
Liber 5 of CORNERS  
on page 93  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

One-quarter corner common to Sections 15 & 22, T44N-R41W.

February 2, 1994

I, John R. Garske, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Quarter section post set by Algemon Merryweather in July 1852 consisting of a 5" hemlock as the corner tree from which a 6" hemlock bears S10°W - 2 links (1.32 feet).

**PEER GROUP**

**Approved**

Richard P. Nealen

9/14/94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original survey information could be found. We found a 1" I.D. iron pipe with an old wood post in poor condition lying on ground. This corner position is shown on a 1927 survey by a D.S. Burnett, a 1960 survey map by W. Tuttle and in a 1972 survey by Joseph Harding. The iron pipe I found is historically in the correct location and is referenced in many deeds of record. It is in a harmonious location being used and accepted by area residents.

Record research on file with County Register of Deeds office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 3/4" x 30" rebar inside existing pipe with a 3 1/4" stamped aluminum county tablet. Established the following bearing trees and reference objects:

- 12" maple - N48°E - 56.07 feet
- 8" maple - N85°W - 18.64 feet
- 12" w. birch - N25°W - 18.34 feet
- P. pole #85-20577 - S21°E - 40.55 feet
- Steel sign post - S45°W - 2.00 feet



Signed by

John R. Garske

Date

2-28-94

Surveyor's Michigan License No. 28410