

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Section 14 T <u>44</u> N R <u>41</u> W	<u>I-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Received for record the
20TH day of AUGUST
A. D. 1998 at 1:15 o'clock
P m., and recorded in
Lib. 7 of CORNERS
on page 38
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner to 10, 11, 14, & 15, T44N, R41W

I, John R. Garske, in a field survey on June 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Wood Post- Township Subdivision by A. Merryweather D.S., June 30, 1852
Original B.T.'s:
Sugar 8" S40°W 23 Links
Sugar 12" N35°E 39 Links

1991- Corner Recorded by Richard Drahn, RLS 21564, L3, pg. 392, 2/14/91. He found an iron pipe with brass cap set by H.S. Tuttle RLS 1777.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2 1/2" pipe with 3 1/4" brass cap stamped S-1777 as per Richard Drahn's certificate.
Bearing trees:
(13") 10" Sugar Maple N66°E 26.15 feet (26.21)
(8") 7" White Ash S16°E 18.76 feet (M & R)
(14") 10" White Ash S89°W 14.31 feet (M & R)
Steel rail N02°W 2.45 feet (M & R)


() measured

(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8" Maple S20°W 35.87 feet (existing)
18" Maple S47°E 40.80 feet (existing)
14" Maple N43°E 35.23 feet (existing)
14" H. Maple N15°W 49.32 feet (new)

DEED GROUP APPROVED
Richard P. Drahn 8/19/98
COUNTY REGISTER



Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 6/30/98