

SURVEY & REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

SECTION

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Section 14 T <u>44</u> N R <u>41</u> W	<u>J-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Received for record the
20TH day of AUGUST
A. D. 1998 at 1:15 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 39

Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner Sections 11 & 14, T44N, R41W

I, John R. Garske, in a field survey on June 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Wood Post- Township Subdivision by A. Merry weather, July 1, 1852
Hemlock 6" S30°E 26 Links
Sugar 14" n35°E 2 Links

1991- Corner Recorded by Richard Drahn, RLS 21564, I.3, pg. 393. He found a brass capped monument set by H.S. Tuttle RLS 1777. Bearing trees:
17" Sugar Maple N15°W 13.7 feet
16" Hemlock S39°W 34.8 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" brasscapped pipe stamped S-1777- set by H.S. Tuttle.
Richard Drahn's Bearing trees are noted as follows:
(10") 9" White Ash N01°W 27.45 feet (existing)
(8") 7" White Ash S41°E 22.54 feet (existing)
11' Hemlock S11°W 31.12 feet (existing)
6' Steel rail N59°W 2.6 feet (existing)
All bearing trees were found in good condition.
() measured

(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 5/8 iron rod S89°-56'-07"W 190.08 feet
Found 5/8" iron rod S89°-56'-07"W 1320.60 feet

PEER GROUP APPROVED

Richard P. Drahn 8/19/98
COURT RECORDED



Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 6/30/98