

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey Section 11	T 44N R 41W	K-4
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Received for record the
10th day of NOVEMBER
 A. D. 1999 at 11:25 o'clock
A m., and recorded in
 Liber 7 of CORNERS
 on page 263
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 corner common to sections 11 & 12

I, John R. Garske, in a field survey on Oct. 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by A. Merryweather in June 1852
 Original Corner: Wood Post
 Original Bearing Trees:
 7" Cedar N32°E 25 links
 10" Balsam S70°W 10 links
 1948 - MDNR survey by Shadko
 1973 - Robert Winat Survey, Bearing Trees:
 10" Hemlock S63°W 23 .1 feet
 10" Hemlock S63°E 32.4 feet
 1997 - Gary Pisoni Survey - notes 2" pipe found

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 2 1/2 " iron pipe at the corner position with a 3/4" iron pipe and cap inside the larger pipe. The 3/4" pipe had a plastic cap stamped "WINAT" for Robert Winat, RLS. An old square cedar post was also found next to the pipe. No evidence of the original bearing trees could be found. I accepted this corner position as it has been used and accepted since at least 1948 as shown on the Shadko survey I obtained from the MDNR. Numerous blazed trees all point to the found location.

(Research on file)

DEED GROUP APPROVED
Richard H. Drahm 11/9/99
 COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the one - quarter corner position I replaced the found iron pipe with a 2 1/2" x 30" aluminum pipe monument with a 3 1/4" dia alum. cap stamped to identify the corner from which I established:

Steel rail N45°W 1.55 feet
 6" maple N54°E 9.16 feet (existing)
 22" Hemlock S62°E 32.93 feet (existing)
 18" Hemlock S64°W 23.80 feet (existing)
 Set D.H. nails & caps in all trees with bearing tree tags.

Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 11-9-99



FLD.BK 235.P211

EDM No G-71 263