

**SURVEY & REMONUMENTATION**

JAN 22 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogetic County } ss.

For corners in  
Gogetic  
(County)

Located In: Corner Code #

1. Public Land Survey	Section 21	45W	39W	F-7
	T	R		
	T	R		
	T	R		
	T	R		
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Received for record the  
2<sup>nd</sup> day of DECEMBER  
A. D. 1997 at 10:35 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 277  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
1/4 corner sections 16 & 21, T45N, R39W

John R. Garske November 13, 97

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S. in 1851. He set a wood post at 40.00 chains running N89°W, from which:  
a Y. Birch 14" S65°W 6 links (3.96 ft.)  
a Hemlock 10" N65°W 6 links (3.96 ft.)  
- Leave swamp - 20.00 chains  
- Enter swamp 55.30 chains

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I set a point from which to search based on a mathematical location from natural feature ties and existing monumented corners in Section 21. From the calculated search point, I located the corner position from the decayed remains of the two original bearing trees at 13.16 feet south and 0.34 feet west. The yellow birch B.T. is now a large mound with yellow birch bark evident and the hemlock is now a large stump hole with bark and decayed remains evident. I positioned the corner from the two bearing trees which checks very good with the two swamp calls in the original notes.

(Research on file)

PEER GROUP APPROVED  
Richard H. Dyer 12/1/97  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" dia. x 30" long alum. pipe with a 3 1/4" dia. alum. cap stamped to identify the corner, from which I established:

8" Maple	N44°E	37.12 feet
9" Maple	S55°E	11.86 feet
9" B. Ash	S24°W	38.74 feet
11" B. Ash	S84°W	30.02 feet
Steel sign post	North	1.60 feet

FLD Bk. No. 197

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 11/28/97

