

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in
Gogebic
 (County)

	Located In:	Corner Code #
1. Public Land Survey	Section 34 45N 39W	G-12
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Received for record the
18TH day of AUGUST
 A. D. 1997 at 11:00 o'clock
A m., and recorded in
 Liber 6 of CORNERS
 on page 176;
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 One-quarter section corner common to sections 33 & 34

John R. Garske July 28 97

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner set by Wells Burt, R.S. in 1851 original bearing trees:
 10" cedar - N14E - 10l
 10" cedar - S59W - 24l

1991 - John Garske positioned the corner by single proportion and recorded it in liber 3, pg. 447.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the 2" aluminum capped iron rod as set in 1991 in the west shoulder of Highway 45. The two reference monuments and bearing trees are all in good condition. No other bearing trees are available but I set a P.K. recessed in the pavement as noted below.

(Record Research on File)

PEER GROUP APPROVED
Richard L. Drabm 8/13/97
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 2" aluminum cap stamped.
 Ref. mon. N29° W 47.53 feet (existing)
 Ref. mon. S38°W 61.30 feet (existing)
 8" spruce S86°W 24.34 feet (existing)
 P.K. nail Due East 4.20 feet (new)
 Edge of pavement East 1.7 feet
 Centerline highway 45 east 16.5 feet



Signed by John R Garske
 Surveyor's Michigan License No. 28410

Date 8/13/97