

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in _____
 Gogebic
 (County)

Located In: _____

Corner Code # _____

- | | | | | | |
|------------------------------------|---|-------|---|-------|-------|
| 1. Public Land Survey | T | 45N | R | 39W | H-9 |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous | S | _____ | T | _____ | R |
| Property in Section | S | _____ | T | _____ | R |

Received for record the
16th day of August
 A. D. 1996 at 2:30 o'clock
P m., and recorded in
 Liber 6 of CORNERS
 on page 33
Richard J. Brown
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

The one-quarter section corner common to Sections 22 & 27, T45NW, R39W.

I, John R. Garske, in a field survey on AUGUST 6, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9							●				
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

On September 10, 1851, Will Burt, U.S. Deputy Surveyor, set a wood post with the following bearing trees:
 10" Y. birch - N50°E - 31 links
 110" Sugar - N65°W - 15 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of the original corner position exists as it now lies in a cultivated field as part of the Toumey Nursery. I established the corner by single proportional measurement, on line and equal distance between the opposing section corners.

 No satisfactory bearing trees or objects are close so I set two witness corners, north and west, of the 1/4 corner location. I did not set anything at the one-quarter corner because of the location.

Record research on file. (See sketch on back.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3' x 2 1/2" aluminum diameter pipe with a 3" diameter aluminum cap as a witness corner and stamped as follows: T45N, R39W, W.C., 1/4, S-22, S-27, 1996, R.L.S. 28410, S0°-22'-71"E, 165 feet with a steel sign rail 0.85 feet away. A second pipe with aluminum cap stamped the same as above except: N89°-16'-83"E, 300 feet with a steel sign rail 0.90 feet away.

PRER GROUP APPROVED
Richard J. Brown 9/12/96
 COUNTY REPRESENTATIVE



Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 9-11-96