

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>40W</u>	<u>H-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }  
Gogebic County }

Received for record the  
4th day of NOVEMBER  
A. D. 1998 at 3:20 o'clock  
P M., and recorded in  
Liber 7 of CORNERS  
on page 83  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner Sections 22 and 27, T45N, R40W

I, Gary L. Pisoni, in a field survey on October 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor on July 27, 1851.

Original Bearing Trees;

Yellow Birch	12"	N 62°E	38 links (25.08 ft)
Yellow Birch	8"	S 88°W	21 links (13.86 ft)

On 4/18/90, Richard L. Drahn RLS with the U.S. Forest Service restored the corner position by single proportionate measurement on line and midway between the Southeast corner and the Southwest corner of Section 22, and at the corner position, set a 3" diameter brass cap embedded in the North blacktop lane of U.S. Hwy. No. 2 and stamped as follows: T45N, R40W, 1/4, S-22, S-27, 1990, RLS 21564, from which he established the following new bearing trees:

Land corner certificate recorded in Liber 3, Page 421 of L.C. Records.

1990 Bearing Trees:

Red Maple	16"	N 16° E	89.05 feet
Red Maple	14"	S 39° W	121.31 feet
White Birch	16"	S 01° W	85.80 feet
Ref. Mon. 3 1/4"x30" Al.Mon.		North	67.69 feet
Steel sign post	6'	North	68.22 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner destroyed during re-pavement of U.S. Highway No. 2. Reset corner position inside a monument box from Richard L. Drahn's bearing trees of 1990.

On 8-31-98 reset corner position from the existing bearing objects: (All measurements taken to a nail in side of tree)

Red Maple	16"	N 16°E	89.05 feet
Red Maple	14"	S 39°E	124.30 feet
White Birch	16"	S 01°W	85.80 feet
Ref. Mon. 3 1/4"x30" Al.Mon.		North	67.69 feet
Steel sign post	6'	North	68.22 feet

Corner record research on file with County Representative.

PEER GROUP APPROVAL  
Richard L. Drahn 10/27/98  
COURT REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position set a 5/8"X30" rebar with a 3" diameter aluminum cap inside a monument box stamped as follows:  
Gogebic County Remonumentation, T45N, R40W, 1/4, S-22, S27, 1998, RLS 27457.

98-G11  
Signed by Gary L. Pisoni Date October 24, 1998

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN. 25, 1975  
REVISED MAY 14, 1975  
NO. REVISED JAN 1998  
REVISED OCT 1995

