

MAY 16 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in Gogebic Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

Received for record the  
17<sup>TH</sup> day of OCTOBER  
A. D. 1996 at 9:50 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 64

Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

- 1. Public Land Survey Section 19 T 45N R 41W A-8  
T 45N R 42W M-8  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

The one-quarter corner common to Sections 19, 24, T45N, R42-41W.

I, John R. Garske, in a field survey on September 24, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

In 1844, William Burt, U.S. Deputy Surveyor, set a wooden post and the following bearing trees:  
36" White Pine - N25°E - 44 links  
9" Yellow birch - N20°W - 9 links

In 1974, Richard Drahn, RLS, set a 2 1/2" pipe with a brass tablet and established the following bearing trees and reference objects:  
7" White spruce - N24°E - 18.3 feet      4" x 4" x 7' cedar sign post - S80°W - 2.6 feet  
9" White spruce - S45°E - 22.6 feet      3" sugar maple - S89°W - 53.5 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the iron pipe with brass tablet. Two bearing trees were still existing as was the cedar sign post. I updated the corner position to State and County specifications as noted below.

P.A. 74 research on file.

PEER GROUP APPROVED  
Richard L. Drahn 10/16/96  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I established or updated the following bearing trees and reference objects:  
7" maple - West - 53.55 feet (existing)  
12" spruce - N28°E - 18.17 feet (existing)  
14" spruce - S25°W - 18.63 feet (new)  
6' steel sign rail - east - 1.09' (new)

All bearing trees were blazed, painted, scribed and tagged.



Signed by John R. Garske Date 10-15-96  
Surveyor's Michigan License No. 28410

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 23, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983