

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ca.

Received for record this

21<sup>st</sup> day of JULY

A. D. 1999 at 1:05 o'clock

P. m., and recorded in

Lib. 7 of CORNERS

on page 169

Ramona Collins Deputy  
Register of Deeds

For corners in  
Gogebic

(County)

Located In: Corner Code #

1. Public Land Survey

Section 29 45N 41W C-11

T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_

2. Property Controlling  
in Section

S\_\_\_ T\_\_\_ R\_\_\_

3. Miscellaneous

S\_\_\_ T\_\_\_ R\_\_\_

Property in Sec.

S\_\_\_ T\_\_\_ R\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

SECTION CORNER 29, 30, 31 & 32, T45N, R41W

I, John R. Garske in a field survey on January 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by A. Merryweather, D.S., 1852

Original Bearing Trees: 12" white pine N10°W 8 links  
10" yellow birch S50°E 32 links

1974-Richard L. Drahn, RLS #21564, corner restored, rec. L1, pg. 192 - He set a 2 1/2" x 5' concrete filled pipe with a 3" diameter bronze tablet stamped, from which:

12" hemlock N56°W 85.8 feet  
15" hemlock S52°E 167.2 feet  
7" tamarack S20°E 36.5 feet  
cedar post S45°W 2.7 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the monument as described above, in good condition. All bearing trees except the 12" Hemlock are dead. I set nails in all the trees and recorded new ties as noted below.

(Research on file)

PEER GROUP APPROVED  
Richard L. Drahn 7/20/99  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument found as described above from which I established the following witnesses:

16" hemlock N53°W 85.55 feet (existing) 85.8'  
4" spruce N81°W 70.65 feet (new)  
3" spruce N22°W 33.67 feet (new)  
steel sign rail east 1.12 feet (new)

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 7/19/99

