

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
29TH day of SEPTEMBER
 A. D. 1993 at 9:15 o'clock
A m., and recorded in
 Liber 4 of CORNERS
 on page 255 279
Betty Lorie Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in
Gogebic
 (County)

Located In: Corner Code #:

1. Public Land Survey	T <u>45N</u> R <u>41W</u>	<u>E-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat PEER GROUP Approved
 5. Private Claims _____
Richard L. Drab 1/20/94

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary L. Pisoni, in a field survey on June 20, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by A. Merryweather, U.S. Deputy Surveyor on June 18, 1852.
 Original corner: Wood post
 Original bearing trees:

Hemlock	30"	S 30°W	18 links (11.88 feet)
Birch	6"	N 35°E	22 links (14.52 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found. Corner position restored through the use of old survey maps. Found an iron pipe marking the meander corner between Sections 32 and 33 and an auger steel pin marking the South 1/16 corner between Sections 32 and 33 according to the old survey maps. Projected the Section line from the meander corner through the South 1/16 corner to the quarter corner position as shown on the old survey maps but could not find the quarter corner. Reset corner position according to the old survey map and above procedure in order to be consistent with older surveys completed in Sections 32 and 33.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: T45N, R41W, 1/4, S-32, S-33, 1991, RLS 27457; from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Sugar Maple	5"	S 85°E	3.48 feet
Sugar Maple	13"	S 07°W	24.71 feet
Hemlock	16"	N 26°W	35.49 feet
Steel sign post		N 30°E	0.65 feet

Signed by Gary L. Pisoni
 Surveyor's Michigan License No. 27457

Date Sept. 20th 1993

