

**SURVEY & REMONUMENTATION**

52

JUN 29 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Gogebic _____ (County)	Located in:	Corner Code #
1. Public Land Survey	T 45N R 41W	I-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }  
Gogebic County } ss.

Received for record the  
23<sup>RD</sup> day of MARCH  
A. D. 1995 at 1:15 o'clock  
P m., and recorded in  
Liber 5 of CORNERS  
on page 220  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Gary L. Pisoni, in a field survey on October 5, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Algernon Merryweather, U.S. Deputy Surveyor on June 11, 1852  
Original Corner: Wood Post  
Original Bearing Trees:  
Sugar 24" S 53°W 12 links (7.92 feet)  
Elm 14" N 65°E 27 links (17.82 feet)  
Richard Drahn, RLS #21564 monumented this corner in July, 1981 and set a 2" X 30" long aluminum pipe monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence remains of the original corner or bearing trees.  
Corner position set by Richard Drahn RLS (U.S.F.S.) found to be in error and not consistent with measurements in surrounding sections. Corner appears to be approximately 60 feet short between the SW corner of Section 2 and the S 1/4 corner of Section 2. I could not accept the monument as set. No other evidence available in the area for restoring the corner position.  
I restored the corner position using Double Proportionate measurement methods between the SW corner of Section 3 and the S 1/4 corner of Section 2 and between the NE corner of Section 3 and the E 1/4 corner of Section 10.

Richard Drahn RLS agreed that I could move his monument to the Double Proportioned position which better represents the true location of the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I reset 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: T45N, R41W, S-3, S-2, S-10, S-11, 1981, RLS- 21564 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Sugar Maple	7"	N 84°E	8.76 feet
Red Maple	7"	S 21°W	35.74 feet
Sugar Maple	7"	N 13°W	15.75 feet
Steel Sign Post		N 75°W	1.06 feet

PEER GROUP APPROVED

Richard Drahn 4/6/95  
COUNTY REPRESENTATIVE

Signed by Gary L. Pisoni Date 4-12-94  
Surveyor's Michigan License No. 27457

