

LAND CORNER RECORDATION CERTIFICATE Register's Office } ss.
Filing Requirement of Act 74, Mich. P.A. 1970 Gogebic County }

For corners in
Gogebic
(County)

Located In: Corner Code #

- 1. Public Land Survey T 45N R 41W I-5
T R
T R
- 2. Property Controlling in Section PEER GROUP Approved
- 3. Miscellaneous Property in Sec. S Richard P. Pisoni 5/20/94

Received for record the
19th day of JUNE
A. D. 1994 at 1:45 o'clock
P m., and recorded in
Liber 5 of CORNERS
page 69
Richard J. Bidunye
Register of Deeds
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner between Sections 10, 11, 14 and 15

I, Gary L. Pisoni, in a field survey on December 16, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Algernon Merryweather, U.S. Deputy Surveyor on June 11, 1852.
Original Corner: Wood Post
Original Bearing Trees:
Hemlock 24" S 46° E 22 links (14.52 feet)
Hemlock 30" N 05° W 11 links (7.26 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence was recovered.
I restored the corner position using double proportionate measurement methods between the Southwest Corner of Section 10 and the Southeast Corner of Section 11, and between the West Quarter Corner of Section 11 and the West Quarter Corner of Section 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: T45N, R41W, S-10, S-11, S-15, S-14, 1991, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)
Red Maple 6" N 13° E 26.15 feet
Red Maple 7" S 81° E 25.95 feet
Red Maple 6" S 69° W 12.97 feet
Steel Sign Post South 0.86 feet



Signed by Gary L. Pisoni Date 4-12-94
Surveyor's Michigan License No. 27457