

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic (County)

Located In:

Corner Code #

- 1. Public Land Survey T 45N R 41W K-7
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner 13, 14, 23 & 24; T.45 N., R.41 W.

I, Richard L. Drahn in a field survey on December 13, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by A. Merryweather on 6/4/1852. Original B.T.s --- 10" Sugar N.10 W. 10 links (6.60') --- 8" Ironwood S.11 E. 38 links (25.08') --- Paul R. Mack, on 4/17/35 recovered a scribed 20" Sugar at this location. John P. Smallwood RLS for MSHD, on 6/8/61 recovered a wood post at this location and set three B.T.s. Richard L. Drahn (21564) on 10/9/89 recovered the original Sugar B.T. still alive and Smallwoods' B.T.s. He set a 2" X 30" alum. monument with a 3 1/4" stamped aluminum cap and the following new B.T.s:

- 8" Sugar Maple N.17 W. 25.74'
- 6" Sugar Maple S.46 E. 13.47'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 8" Sugar Maple S.74 W. 19.85'
- 6' Steel sign rail S.80 E. 2.5'

Corner recorded in Gogebic County Liber 3, Page 302 on 1/23/90.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- 11" Sugar Maple N.20 W. 25.72'
- 8" Sugar Maple S.27 E. 13.47'
- 9" Sugar Maple S.75 W. 19.88'
- 6' Steel sign rail S.81 E. 2.49'

The original Sugar B.T. is still alive and is 27" in dia.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- 4" Sugar Maple N.81 E. 17.93'

All bearings magnetic. Area shows evidence of strong magnetic attraction.

DEER GROUP APPROVED

Richard L. Drahn 12/19/97
COUNTY REGISTER

Signed by Richard L. Drahn Date December 15, 1997

Surveyor's Michigan License No. 21564

Register's Office }
Gogebic County } ss.

Received for record the
22ND day of DECEMBER
A. D. 1997 at 11:00 o'clock
A m., and recorded in
Liber 6 of CORNELIS
on page 294
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

