

SURVEY & REMONUMENTATION

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>45N</u> R <u>43W</u> | <u>G-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Received for record the
16TH day of AUGUST
A. D. 1996 at 10:30 o'clock
A m., and recorded in
Liber 5 of CORNERS
on page 399
Ramona Collins Deputy
Register of Deeds
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner comm. to sec's. 29, 30, 31 & 32

I, John P. Goss, in a field survey on July 20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by Algernon Merryweather, July 29, 1852. set post.

Original bearing trees: Sugar 8" N 80° E 20 links
Birch 12" S 89° W 12 links

James D. Rein RLS 26464 recorded this corner in Liber 2 pages 272 and 273 of Land Corners for Gogebic County. He found a 1" iron pipe. He set a 3/4" by 36" long reb with a 2" dia. aluminum cap marked: T45N, R43W; S-29, S-30, S-31, S-32, 26464, 1982, 6 inches below road surface with the following witnesses: 12" Maple-Sugar- N 46° W- 45.0'; the following 3/4" by 36" rebar with 2" aluminum cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1. S 01°-43'-13" W 48.00'
2. S 43°-54'-10" E 69.69'

I found 3/4 inch rebar with 2 inch aluminum cap at 6 inches below road surface and it checked with James Rein certification for witnesses bearing and distance. I updated the accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP
Richard H. Drain 8/8/96
COURT REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 3/4 inch rebar with 2 inch aluminum cap I established the following existing and new bearing trees and reference objects.

- D.H. Nail in 14" Sugar Maple N 46° W 44.50'
D.H. Nail in 23" Hemlock N 72° E 19.00'
6' rail and sign N 13° E 3.35'

Reference monuments consisting of 3/4 inch by 36 inch rebar with 2 inch aluminum cap.

1. S 01°-43'-13" W 48.00'; 6' rail & sign- 0.60'
2. S 43°-54'-10" E 69.69'; 6' rail & sign- 0.94'

Signed by John P. Goss

Date July 21, 1996

Surveyor's Michigan License No. 23509

