

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
12<sup>TH</sup> day of MAY  
A. D. 1999 at 10:55 o'clock  
A. m., and recorded in  
Liber 7 of CORNERS  
on page 108  
Ramona Collins Deery  
Register of Deeds

For corners in SECTION

<u>Gogebic</u> (County)		Located In:	Corner Code #:
1. Public Land Survey	T 46N R43W		E-13
	T _____ R _____		
	T _____ R _____		
	T 45N R43W		E-1
2. Property Controlling in Section	S _____ T _____	R _____	
3. Miscellaneous Property in Sec.	S _____ T _____	R _____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

Section Corner 32, 33, 4 & 5; T.45-46 W., R.43 W.

I, Richard L. Drahn in a field survey on April 17, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5	4		3		2		1		
3												
4	7		8	9		10		11		12		
5												
6	18		17	16		15		14		13		
7												
8	19		20	21		22		23		24		
9												
10	30		29	28		27		26		25		
11												
12	31		32	33		34		35		36		
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/6/1847. Original B.T.s --- Hemlock 16" N.23 E. 25 links (16.50') --- Hemlock 30" N.53 W. 5 links (3.30') --- Hemlock 12" S.70 E. 25 links (16.50') --- Hemlock 10" S.35 W. 15 links (9.9')---

Corner restored by Donald D. Lappala, RLS 12585 on 6/15/66 from the remains of the four original B.T.s and a natural feature tie north. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 6" Sugar Maple S.60 E. 49.8' --- 4" Sugar Maple S.00½ E. 10.8' --- 7" Yellow Birch S.81 W. 16.0' ---

Corner recorded in Gogebic County USFS Liber, Page 1-9 on 9/1/67.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:

6"	downed Sugar Maple	S.62 E.	---
7"	Sugar Maple	S.02 E.	10.75' (new nail)
10"	Yellow Birch	S.83 W.	15.84' new nail)

New bearing trees by USFS 3/16/92.

15"	Yellow Birch	S.66 E.	20.84'
6'	Steel sign rail	S.02 E.	1.52'

Shallow depressions are all that remain of the original B.T.s.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

6'	Steel fence rail	N.88 E.	2.29'
6'	Steel fence rail	N.88 W.	7.48'

Richard L. Drahn 5/11/99  
GOGEBIC COUNTY



Signed by Richard L. Drahn

Date April 21, 1999

Surveyor's Michigan License No. 21564