

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Section 8 ⁴⁵ T _{45N} R _{43W} E-3	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Received for record the
26th day of AUGUST
A. D. 1999 at 1:35 o'clock
P m., and recorded in
Liber 7 of CORNERS
as page 217
Ramona Colman, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner to 4, 5, 8 & 9, T45N, R43W
John R. Garske August 5, 99

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3				●								
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner set by Algernon Merryweather, D.S., July 1852.
Original Bearing trees:
A Spruce 6" S55°-12 links
A Balsam 6" N75°-3links

BEER GROUP APPROVED
Richard L. Dresher 8/24/99
COUNTY REGISTER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I positioned the corner search area using the U.S. Forest Service G.M.M. coordinate system for T45N, R43W. The corner position falls in an old beaver meadow with no standing trees. At approximately 4.3 feet SWly of the math point I found the decayed remains of the spruce bearing tree, consisting of reddish decayed matter and spruce bark. I believe this to be the only spruce in the area and the original bearing tree. The GLO calls west to ascend ridge (4.25 chs.) 50 ft. high and descend ridge (6.25 chs) 50 ft high are consistent with this corner location.
(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set 2 - 4 sections of 3/4" dia. alum. rod with a 3 1/4" dia. alum. cap stamped to identify the corner, from which I established:
Steel sign rail N56°E 13.44 feet
Steel sign rail S64°E 12.47 feet
Steel sign rail S40°W 11.63 feet
Steel sign rail N62°W 10.71 feet

Signed by John R Garske
Surveyor's Michigan License No. 28410

Date 8/24/99

