

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
26TH day of AUGUST
A. D. 1999 at 1:35 o'clock
P m., and recorded in
Lib. 7 of CORNERS
on page 218
Ramona Collins Deputy
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located in:	Corner Code #
1. Public Land Survey Section 8	<u>T45N R43W</u>	<u>E-4</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner to 8, 9, T45N, R43W
John R. Garske August 18, 99

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner set by Algernon Merryweather, D.S., July 1852.
Original Bearing trees:
A. Balsam 6" S63°E 15 links
A Spruce 6" N55°W 2 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I searched for evidence of the original corner position from a math point with nothing found. I set the corner at a single proportional location, on line and at the mid point between section corners in accordance with the original notes. This location is consistent with the GLO natural feature tiles.
(Research on file)

DEED GROUP APPROVED

Richard R. Dralun 8/24/99
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" x 4 foot long alum. rod with a 3 1/4" dia. alum. cap stamped to identify the corner from which:
8" B. Ash S15°W 40.83 feet
10" Balsam S33°E 60.73 feet
8" B. Ash S47°E 48.07 feet
Steel Sign rail N41°W 1.47 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 8/24/99 No. 28410

