

**SURVEY & REMONUMENTATION**

NOV 12 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey	Section 26	T 45N	R 43W	J-9
		T	R	
		T	R	
		T	R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Register's Office }  
Gogebic County } ss.

Received for record the  
9<sup>th</sup> day of OCTOBER

A. D. 1997 at 11:00 o'clock  
A m., and recorded in

Lib. 6 of CORNERS  
on page 244.

Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No: \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 corner sections 23 and 24, T45N, R43W

I, John R. Garske, in a field survey on June/Aug 19 97 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Algernon Merryweather, D.S. in 1852  
1/4 corner set @ 40.07 chains from which:  
A sugar 6" S30°W 9 links  
A sugar 6" N10°E 17 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner by single proportional measurement on line and equidistant between opposing section corners. This corner position is consistent with natural feature ties including the north bend of lake @ 54.25 chains west.

(Research on file)

**PLANS GROUP APPROVED**  
Richard L. Dralun 10/18/97  
COUNCIL REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" x 30" alum. monument with a 3 1/4" dia. alum. cap stamped to identify the corner, from which I established:

Sugar 6"	North	3.65 feet
Sugar 11"	S59°E	23.22 feet
Sugar 13"	S18°E	10.21 feet
Sugar 5"	S63°W	13.98 feet
Steel sign rail	South	0.78 feet

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 10/7/97

