

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
12 day of MAY

A. D. 19 99 at 10:30 o'clock

A m., and recorded in
Liber 7 of CORNERS

on page 131

Ramona Collins, Deput
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located in:

Corner Code #

1. Public Land Survey

T46NR43W K-13

T R

T R

T45NR43 K-1

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner 35, 36, 1 & 2; T.45-46 N., R.43 W.

Richard L. Drahn in a field survey on April 2019 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/5/1847. Original B.T.s --- Hemlock 12" N.11 E. 25 links (16.50') --- Y. Birch 12" N.73 W. 38 links (25.08') --- Hemlock 8" S.30 E. 28 links (18.48') --- Birch 6" S.35 W. 35 links (23.10')

Corner position restored by Donald D. Lappala RLS 12585 on 9/29/69 from the remains of the 1st, 2nd and 4th original B.T.s He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 8" Cedar N.22 E. 29.1' --- 7" Cedar S.82 E. 27.5' --- 14" Yellow Birch S.85 W. 31.7. ---

Corner recorded in Gogebic County USFS Liber, Page A-21 on 4/8/70.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:

10"	Cedar	N.21 E.	29.10'	(new nail)
9"	Cedar	S.81 E.	27.51'	(new nail)
16"	Yellow Birch	S.85 W.	31.75'	(new nail)

Fragments of Hemlock wood and bark remain from the first original B.T. and large depressions still remain from the 2nd and 4th B.T.s.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

4"X4"X7' Cedar sign post N.54 E. 2.96'

6' Steel sign rail S.03 W. 2.69'

Richard L. Drahn 5/11/99
COUNTY



Signed by Richard L. Drahn

Date May 2, 1999

Surveyor's Michigan License No. 21564

USFS A-21