

SURVEY & REMONUMENTATION

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
9th day of OCTOBER
A. D. 1997 at 11:00 o'clock
A m., and recorded in
Liber 6 of GOGBIC
on page 231
Ramona Collins, Deputy
Register of Deeds

For corners in
Gogebic
(County)

Located In: Corner Code #
Section 26 45N 43W K-9
T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section corner to 23, 24, 25 & 26 T45N, R43W.

I, John R. Garske, in a field survey on June/Aug 19 97 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Algernon Merryweather, D.S. in 1852
Original BT's:
Hemlock 20" N40°W 8 links
Sugar 8" S75°E 27 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

PEER GROUP APPROVED
Richard P. Drain 10/8/97
COUNTY REPRESENTATIVE

I established the corner position by using a series of natural feature ties from the original notes, the two stream crossings to the north at 22.50 chains (1485.20') in the bottom of a ravine and 39.50 chains (2607.0'), the enter swamps call west, 10 chains (660') and the north bend of the lake call @ 54.25 chains west (Ormes lake). The entire area is heavily cut over with no evidence of the original bearing trees or any subsequent surveys. These natural feature ties in combination with measurements to monumented corners north 2648.18 west 5260.51' and south 5226.02 assist in verifying the corner. No other location would check with the natural feature ties and to other corners.

(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" x 30" alum. monument with a 3 1/4" dia. alum. cap stamped to identify the corner, from which I established:
10" Sugar N47°W 10.74 feet
10" Sugar N35°E 14.83 feet
10" Twin White Birch S24°W 9.53 feet
Steel sign rail 1.69 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date _____

