

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Section 32 T <u>45N</u> R <u>43W</u>	<u>DE-11E</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u>007</u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register's Office }
Gogebic County } ss.

Received for record the
14TH day of MAY
A. D. 1998 at 3:00 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 330.

Ramona Collins
Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

East M.C. on West Shore between sections
29 & 32, T45N, R43W

I, John R. Garske, in a field survey on April 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

32.5°

Original survey by Algernon Merryweather, D.S. in 1852.
A cedar 6" is the Meander Corner.
No bearing trees.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no original information on the corner location, however, a 1975 W.M.C. survey by Robert Winat, RLS shows a 1" iron pipe with cap set, which I found. I accepted the iron pipe after checking it with other points found including Winat's survey of 5 lots.

(Research on file)

(sketch on back)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the iron pipe at the East M.C. of the Peninsula with a 3 1/4" stamped aluminum cap on a 2 1/2" diam. x 30" long aluminum pipe from which I established:

5" Balsam	S71°W	22.72 feet
5" Balsam	N44°W	31.81 feet
5" Balsam	N15°W	37.75 feet
8" Balsam	NS4°E	20.67 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 5/12/98

PEER GROUP APPROVED
Richard L. Drain 5/13/98
COUNTY BARABEN-44318



