

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

GOGEBIC COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 44 W. <u>T. 45 N. R. 44 W.</u>	A-13 <u>A-1</u>
2. PROPERTY CONTROLLING IN SECTION	T. 46 N. R. 45 W.	M-13
3. MISCELLANEOUS PROPERTY IN SECTION	T. 45 N. R. 45 W.	M-1
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Township corner 31, 36, 1 and 6; T45-46N., R44-45W.

Register's Office }
Gogebic County } ss.

Received for record the
5th day of JANUARY
A. D. 1994 at 10:05 o'clock
A m., and recorded in
Liber 4 of CONCORD
on page 353
Betty Lussie Rapudy
Register of Deeds

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Richard L. Drahn do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 25 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on August 27, 1847.
Original bearing trees:

Y. Birch	14"	S.84°W.	23 links	(15.18 feet)
Y. Birch	12"	N.41°E.	33 links	(21.78 feet)

No record of subsequent corner restoration found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Restored corner at record bearing and distance from the remains of the original bearing trees. The first is now a series of large yellow birch roots that have been disturbed by a log decking area. The second one is now a 20-24" decayed yellow birch stump.

Original corner location lays within 2.1 feet of a N-S mathematical analysis of over five miles of range line between ranges 44 and 45 West, Townships 45 and 46 North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" outside diameter by 6 foot long aluminum rod monument with a 3" cast aluminum cap, stamped to read T.45-46N., R.44-45W.; S-31, S-6, S-1, S-36; 1993; R.L.S. 21564. From which I have established the following new blazed and scribed bearing trees:

10"	Hemlock	N.02°W.	31.70 feet
10"	Hemlock	N.76°E.	46.88 feet
13"	Yellow Birch	S.12°W.	13.94 feet
6'	Steel rail	S.19°W.	2.14 feet

PEER GROUP APPROVED

Richard L. Drahn 1/20/94

SIGNED BY _____ COUNTY REPRESENTATIVE DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Richard L. Drahn MICHIGAN REGISTERED LAND SURVEYOR DATE December 22, 1993 (SEAL)



FED. Z-1

SURVEYOR'S MICHIGAN REGISTRATION NO. 21564