

**SURVEY & REMONUMENTATION**

AUG 08 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

Received for record the  
13<sup>th</sup> day of MAY  
 A. D. 1997 at 1:55 o'clock  
P M., and recorded in  
 Liber 6 of CORNERS  
 on page 111  
Ramona Collins, Deputy  
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N.</u> R <u>45W.</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Sec. Cor. 8, 9, 16, & 17; T.45 N., R.45 W.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Richard L. Drahn in a field survey on May 1, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Austin Burt on August 8, 1851. Original B.T.s --- 10" Hemlock S.65 W. 33 links (21.78') --- 10" Hemlock N.45 E. 6links (3.96') ---

Corner position re-established by Bill Stuth, Wisc. Surveyor in 1984 by mathematical means on a survey along portions of the State Line. He set a 5" Cedar post at his corner location.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Restored corner position from the decayed remains of the two original B.T.s. The first is a large series of root holes with fragments of hemlock bark and wood. The second one is now a 16-20" hemlock stump decayed to below ground line.

Cedar post by Stuth bears S.33 W. 1.9ft. from the original corner location.

Research form on file with Gogebic County records.

**PEER GROUP APPROVED**

Richard L. Drahn 5/12/97  
 COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner location I set a 2" by 30" alum. monument with a 3 1/4" alum. cap stamped to indicate the corner designation. From the monument I established the following new bearing objects:

8"	Sugar Maple	N.38 W.	21.70 ft.
6"	Sugar Maple	S.64 E.	10.87 ft.
6"	Red Maple	S.44 W.	33.66 ft.
6'	Steel sign rail	N.05 E.	2.52 ft.



Signed by Richard L. Drahn Date May 8, 1997

Surveyor's Michigan License No. 21564