

NOV 12 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.  
Gogebic County }

Received for record the  
9<sup>TH</sup> day of OCTOBER  
A. D. 1997 at 11:06 o'clock  
A m., and recorded in  
Liber 6 of CORNEES  
on page 238  
Ramona Collins, Deputy  
Register of Deeds

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

Section 2 T 45N R 45W

J-3

T	R	
T	R	
T	R	
T	R	
S	T	R
S	T	R
S	T	R
S	T	R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

The one quarter section corner common to sections 2 and 3, T46N, R42W.

I, John R. Garske, in a field survey on August, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3									●			
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by Austin Burt, D.S. in 1851  
Set a wood post from which:  
Hemlock 16" S41E 12links-(7.92')  
Hemlock 10" N45W 7links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found an old wood post at the corner position at the intersection of blue lines. A Keweenaw tag on a 30" Y. Birch bears N78°E, 17.6 feet. I also found a 30" Hemlock stump badly decayed which checks with GLO B.T. of S41°E - 7.92'. This position is also consistent with GLO natural feature ties of 2 chains east to enter swamp and 10 chains west to leave swamp. I monumented this location as the original position of the 1/4 corner.

(Research on file)

**PEER GROUP APPROVED**  
Richard P. Dzahn 10/8/97  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set 3/4" dia. x 48" alum. rod with a 3 1/4" dia alum. cap stamped to identify the corner; from which I established the following:

14" Hemlock	S89°W	25.30 feet
14" Hemlock	N08°W	17.76 feet
7" Balsam	S47°E	7.30 feet
4" Cedar post with sign	N80°E	1.26 feet
30"Y. Birch	N78°E	17.6 feet

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 10/7/97

