

**SURVEY &
REMONUMENTATION**

NOV 12 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
9TH day of OCTOBER
A. D. 19 97 at 10:50 o'clock
A m., and recorded in
Liber 6 of CORNERS

on page 220
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in _____

Gogebic (County) Located In: _____ Corner Code # _____

Public Land Survey T 46N R 46W C-13

T _____ R _____

T _____ R _____

T 45N R 46W C-1

Property Controlling S _____ T _____ R _____

in Section S _____ T _____ R _____

Miscellaneous S _____ T _____ R _____

Property in Sec. S _____ T _____ R _____

Lot No. _____ Recorded Plat _____

Private Claims _____

Section Corner 5, 6, 31 & 32; T.45-46 N., R.46 W.

Richard L. Drahn in a field survey on October 2, 19 97,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 16 | 17 | 18 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
Corner established by John Burt on August 31, 1847. Original B.T.s ---
Cedar 12" N.70 E. 34 links (22.44') --- Sugar 16" N.19 W. 8 links (5.28')
--- Hemlock 18" S.60 W. 64 links (42.24') --- Y. Birch 22" S.72 E. 12 links
(7.92') ---

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Restored corner position at record bearing and distance from the remains
of the last three bearing trees. The Sugar is now a large windthrown stump
hole and the Hemlock and Y. Birch are now badly decayed stumps. The 27.10
chain distance west to the recovered C.C. of sec's 31 & 6 and the 7.93 chain
distance south to the recovered C.C. of sec's 5 & 6 are in accordance with
the field notes of the original Government survey. No evidence remains
from the original Cedar B.T.

Research form on file with Gogebic County records.

PEER GROUP APPROVED
Richard L. Drahn 10/6/97
COUNTY REPRESENTATIVE

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
At the corner position I set a 2" X 30" aluminum pipe with a 3 1/4" aluminum
cap stamped to indicate the corner position and the following new B.T.s:

- 7" Sugar Maple S.12 E. 15.08'
- 11" N. Red Oak S.70 W. 26.24'
- 7" Sugar Maple N.16 E. 14.28'
- 6' Steel sign rail N.13 W. 2.31'



Signed by Richard L. Drahn Date October 6, 1997

Surveyor's Michigan License No. 21564