

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in SECTION

Received for record the
21st day of JULY
A. D. 1999 at 1:05 o'clock
P. m., and recorded in
Liber 7 of CORNERS
page 173
Ramona Collins Depate
Register of Deeds

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 45N R 46W</u>	<u>D-1</u>
	T R	
	T R	
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 5 & 32; T.45-46 N., R.46 W.

I, Richard L. Drahn, in a field survey on July 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on 8/31/1847. Original bearing trees:
Cedar 10" N.66° E. 15 links (9.90')
Hemlock 8" N.71 W. 14 links (9.24')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at record bearing and distance from the remains of the two original bearing trees. The first is a series of root holes (species undetermined). The second one is now a 14-20" Hemlock stump, decayed to near ground level.

The 5.00 chain distance west from corner to "Enter swamp, NW and the 40.00 chain distance east and west to recovered section corners is in accordance with the field notes of the original Government survey.

A 4" X 4" X 4 1/2' cedar post bears S.03° E. 52.8' from the original corner location.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" x 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree)

Sugar Maple	6"	N.76° W.	9.63'
Red Maple	9"	N.42° E.	15.03'
Sugar Maple	7"	S.39° E.	27.42'
Steel sign rail	6'	N.23° E.	1.99'

DEED GROUP APPROVED
Richard L. Drahn 7/20/99
COUNTY REGISTERED



Signed by Richard L. Drahn Date July 15, 1999
Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1996