

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County

Received for record the
21st day of JULY
A. D. 1999 at 1:05 o'clock
P. M., and recorded in
Liber 7 of CORNERS
on page 175
Ramona Collins Deputy
Register of Deeds

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| <u>Gogebic</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | <u>T 45N R 46W</u> | <u>H-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 3 & 34; T.45-46 N., R.46 W.

I, Richard L. Drahn, in a field survey on July 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on 8/31/1847. Original bearing trees:
Cedar 6" N.72° E. 23 links (15.18')
Hemlock 12" N.40° W. 27 links (17.82')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner position restored at record bearing and distance from the remains of the two original bearing trees. The first is an almost completely decayed 10-14" Cedar windfall. The second one is now a large, almost completely decayed dead in place hemlock stump. Only portions of Hemlock bark and fragments of Hemlock wood remains. The 1.50 chain distance east to "Enter swamp, NW" and the 3.00 chain distance west to "Leave swamp, NE" are in accord with the field notes of the original Government survey.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree)

| | | | |
|-----------------|-----|----------|--------|
| Yellow Birch | 7" | S.19° E. | 10.40' |
| Cedar | 12" | N.21° W. | 22.80' |
| Black Ash | 5" | S.89° W. | 4.92' |
| Steel sign rail | 6' | N.78° E. | 2.11' |

PEER GROUP APPROVED
Richard L. Drahn 7/20/99
COUNTY REGISTERED



Signed by Richard L. Drahn Date July 13, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1993
REVISED OCT., 1995