

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County }

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>46W</u>	<u>1-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the
21ST day of JULY
A. D. 1999 at 1:15 o'clock
P M., and recorded in
Liber 7 of CORNERS
on page 177
Ramona Collins Duvette
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 2 & 3; T.45 N., R.46 W.

I, Richard L. Drahn, in a field survey on July 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3	●	2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 6/27/1851. Original bearing trees:
Y. Birch 14" S.64 W. 13 links (8.58')
Sugar 6" N.43 E. 30 links (19.80')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner position restored at record bearing and distance from the remains of the two original bearing trees. The first is portions of a large, badly decayed Yellow Birch windfall. The second one is now a shallow windthrown stump hole. The 2.00 chain distance south to "Enter swamp, NE" although indistinct, checks to the start of a Alder - Swamp grass cover type.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree)

Cedar	10"	N.43 W.	19.50'
Black Ash	10"	S.79 E.	26.04'
Cedar	12"	S.08 W.	2.59'
Steel sign rail	6'	N.23 E.	2.23'

PEER GROUP APPROVAL
Richard L. Drahn 7/20/99
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date July 13, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976