

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } m.

Received for record the
10th day of JUNE
A. D. 1999 at 10:05 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 153
Ramona Collins Deputy
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>46W</u>	<u>J-3</u>
	T____ R____	_____
	T____ R____	_____
	T____ R____	_____
2. Property Controlling in Section	S____ T____ R____	_____
	S____ T____ R____	_____
3. Miscellaneous Property in Sec.	S____ T____ R____	_____
	S____ T____ R____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3									●			
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Quarter Corner 2 & 11; T.45 N., R.46 W.
I, Richard L. Drahn, in a field survey on June 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt on 6/28/1851. Original bearing trees:
Hemlock 10" S.23 W. 21 links (13.86')
Hemlock 12" N.35 E. 31 links (20.46')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Corner position restored at record bearing and distance from the remains of the two original B.T.s. The first is a 16-20" very badly decayed Hemlock stump. The second one is now a series of foot holes with fragments of Hemlock wood and bark.
Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
At the corner position I set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s:

Sugar Maple	9"	North	21.06'
Sugar Maple	11"	S.86 E.	32.47'
Sugar Maple	9'	S.46 W.	19.13'
Steel sign rail	6'	N.34 E.	1.35'

DEED GROUP APPROVED
Richard L. Drahn 6/9/99
COUNTY REGISTER



Signed by Richard L. Drahn Date June 5, 1999
Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983