

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T45N R46W	K-3
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Received for record the
10th day of JUNE
A. D. 1999 at 10:05 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 155
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 1, 2, 11 & 12; T.45 N., R.46 W.

I, Richard L. Drahn, in a field survey on June 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3											●		
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 6/28/1851. Original bearing trees:

Tamarack	14"	S.42° E.	47 links (31.02')
Tamarack	14"	N.75° W.	14 links (9.24')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner position restored at record bearing and distance from the remains of the two original bearing trees. The first is a 16-20" downed tamarack. The second one is now a badly decayed 14-18" Tamarack stump.

An original scribed 14" Tamarack stub witness tree bears S.37°W., 30.0'.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 5' aluminum rod monument with a stamped 3 1/4" aluminum cap and the following new B.T.s:

Cedar	7"	N.62° W.	42.89'
Cedar	12"	N.03° E.	45.30'
Cedar	7"	S.74° E.	14.63'
Steel sign rail	6'	S.54° W.	2.12'

PEER GROUP APPROVED

Richard L. Drahn 6/9/99
COUNTY REGISTER



Signed by Richard L. Drahn

Date June 5, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971