

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County

SECTION

For corners in

Gogebic
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 45N R 45W A-2
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Received for record the:
12th day of MAY
 A. D. 1999 at 11:00 o'clock
A. m., and recorded in
 Liber 7 of CORNERS
 on page 96
Ramona Collins, Dep.
 Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1/4 Corner 1 & 6; T.45 N., R.45-46 W

Richard L. Drahn, in a field survey on March 17, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 8/30/1847. Original B.T.s --- Y. Birch 22" N.45 W. 3 links (1.98') --- Fir 8" S.72 E. 22 links (14.52') ---

C.E. Limpert in 1935 recovered a squared 5" Sugar marking the approximate corner and placed a location poster on the West side of a 20" Hemlock.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored the corner position at record bearing and distance from the remains of the two original B.T.s. The first is a very large series of root holes with fragments of wood and Yellow Birch bark. The second one is now a shallow depression. The 2.00 chain distance south to "enter swamp" and the 2.00 chain distance north to "top of ridge" are in accordance with the original field notes. No evidence found of the 1935 squared sugar or Hemlock tag tree. 17" squared Hemlock bears N.15 E. 96 feet. A 10" Squared Cedar bears N.18 E. 89 feet.

Corner research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new bearing objects.

- 8" Sugar Maple N.31 E. 9.23'
- 7" Sugar Maple S.39 W. 27.22'
- 7" Sugar Maple S.56 E. 17.84'
- 6" Steel sign rail N.61 W. 1.81'

PEER GROUP APPROVED

Richard L. Drahn 5/11/99
COUNTY REGISTER



Signed by Richard L. Drahn

Date March 19, 1999

Surveyor's Michigan License No. 21564

USFS C-25