

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County

Received for record the
12th day of MAY
A. D. 1999 at 11:00 o'clock
A m., and recorded in
Lib. 7 of CORNERS
on page 97
Ramona Collins, Dep.
Register of Deeds
Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>45W</u>	<u>A-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T <u>45N</u> R <u>46W</u>	<u>M-3</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Section Corner 1, 12, 6 & 7; T.45 N., R.45-46 W.

Richard L. Drahn, in a field survey on March 17, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3	7	8	9	10	11	12						
4												
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 8/30/1847. Original B.T.s --- Cedar 12" S.26 E. 13 links (8.58') --- Cedar 12" N.15 W. 5 links (3.30') --- Spruce 6" S.68 W. 23 links (15.18') --- Cedar 8" N.54 E. 12 links (7.92') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at record bearing and distance from the remains of the four original bearing trees. The first is now a shallow windthrown stump hole. The second is now a 14-18" broken Cedar stub with portions of both GLO blazes. (N.35 W. 3.3'). The third is now a shallow stump hole. The fourth one is now a 10-12" badly decayed, downed Cedar with portions of the chest high blaze still evident. The 3.00 chain distance north to "leave swamp, E-W" and the 2.00 chain distance north to "top of ridge 15' E-W) are in accordance with the original field notes.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' aluminum rod with a 3 1/4" stamped aluminum cap and the following new bearing objects:

4"	Sugar Maple	N.21 W.	34.34'
16"	Cedar	S.52 E.	51.14'
13"	Cedar	S.14 W.	29.44'
6'	Steel sign rail	S.52 W.	1.83'

PEER GROUP APPROVED

Richard L. Drahn 5/11/99
COUNTY REGISTER



Signed by Richard L. Drahn Date March 19, 1999

Surveyor's Michigan License No. 21564