

map  
COMP.

# SURVEY & REMONUMENTATION

JUN 29 1995

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
2<sup>ND</sup> day of MARCH  
A. D. 1995 at 9:10 o'clock  
A M., and recorded in  
Liber 5 of CORNERS  
on page 210  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in  
Gogebic  
(County)

Located In: Corner Code #

|                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>46N</u> R <u>42W</u> | <u>B-5</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_  
1/4 Corner 7 & 18; T.46N., R.42W.

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Richard L. Drahn in a field survey on April 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by A. Merryweather, U.S. Deputy Surveyor, on August 19, 1851. Original bearing trees:

|         |     |        |          |              |
|---------|-----|--------|----------|--------------|
| Hemlock | 10" | N.75W. | 19 links | (12.54 feet) |
| Birch   | 12" | S.55E. | 20 links | (13.20 feet) |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No G.L.O. evidence remains. Re-established corner position on line between and proportionate distance from the southeast and southwest section corners of Section 7; T.46N., R.42W.


PEER GROUP APPROVED

Richard L. Drahn 3/1/95  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" diameter by 30" long aluminum monument with a 3 1/4" aluminum cap with magnet stamped to read: T.46N., R.42W.; 1/4; S-7, S-18; 1994; R.L.S. 21564 from which I established the following new blazed and scribed bearing trees and/or objects:

|     |             |        |            |
|-----|-------------|--------|------------|
| 9"  | Sugar Maple | N.20E. | 26.39 feet |
| 8"  | Sugar Maple | S.29E. | 33.49 feet |
| 10" | Red Maple   | S.68W. | 31.79 feet |
| 6'  | Steel Rail  | N.13E. | 1.94 feet  |



Signed by Richard L. Drahn

Date February 6, 1995

Surveyor's Michigan License No. 21564